

Kogge

A Hanseatic cog in squares, triangles and quarter circles

The cog was the ship of the Hanseatic League, the league of merchant towns led by Lübeck that dominated trade on the Baltic and the North Sea from the 13th to the 15th century. The best-preserved cog ever found was built around 1380 and raised from the river Weser at Bremen in 1962. This quilt draws one in the modular manner of the Icelandic artist Siggí Eggertsson: every square of a grid holds one simple shape, and quarter circles turn hard pixels into a round hull, rolling waves and a rising sun.

FINISHED SIZE

120 × 120 cm

GRID

24 × 24 units of 5 cm

PIECES

82 cut pieces, 9 triangle units, 29 quarter-circle units

FABRICS


9: sky and navy by the metre, the rest in small cuts

LEVEL

Intermediate

TECHNIQUES

Rotary cutting, half-square triangles, fusible appliqué, straight-seam piecing




Four shapes, one grid

Each square of the 24×24 grid holds a square of one fabric, a half-square triangle, or part of a quarter circle. Stacking smaller quarter circles on bigger ones gives the rings that bend the copper plank band round the bow and stern, curl the waves and colour the rising sun.

The cog. One mast and one square sail, castles fore and aft, and a rudder hung on the sternpost. Cogs were among the first northern ships to steer that way instead of with an oar over the side.

The flag. White over red is the flag of Lübeck, the leading city of the League. Red and white are still the colours of the old Hanseatic towns.

The herring. Salted Baltic herring, preserved with salt from Lüneburg, was one of the trades that made the Hanse rich, so a shoal swims along with the ship.



The modules. A quarter circle is a background square with a quarter disc appliquéd into one corner; rings are smaller discs stacked on top.

MATERIALS

What you need

MATERIAL	AMOUNT	USED FOR
 Sky S	1.1 m	Background above the waterline
 Sun gold U	1 fat quarter 50 × 55 cm	Sun
 Hanse red R	1 fat quarter 50 × 55 cm	Sail stripes, pennant, flag, sun
 Sailcloth W	0.4 m	Sail stripes, flag, herring
 Copper C	0.5 m	Castles, planking, sun
 Oak brown B	0.4 m	Hull, mast, yard, rudder
 Teal T	0.5 m	Waves
 Aqua A	1 fat quarter 50 × 55 cm	Wave crests
 Baltic navy N	1.1 m	Deep sea, gulls, binding
Backing	135 × 135 cm	Piece it if your fabric is narrower
Batting	135 × 135 cm	Thin cotton keeps a wall quilt flat
Fusible web	1.2 m, 45 cm wide	Paper-backed, for the quarter circles
Hanging sleeve	22 × 115 cm	Leftover backing works
Thread	Grey cotton, 50 wt	Plus thread to match each appliqué colour

Fabric choice. Solids or tone-on-tone prints keep the shapes crisp. Check that the sky, the sail cloth and the aqua read clearly apart, and that the navy is the darkest fabric.

Tools: rotary cutter, mat and long ruler, a square ruler of at least 6.5 cm, an iron and pressing cloth, a pencil, and a compass or a strip of card for the two largest arcs.

How this pattern works

Seam allowance

All sizes include 0.75 cm seams. Sew six 6.5 cm scrap squares into a row: it must be 31.5 cm long, give or take 2 mm. If it is shorter your seams are too wide, if longer too narrow: adjust and sew a new row. It matters: with every seam 1 mm too wide, section 1 comes out 2.2cm narrower than the hull below it.

Grid

One grid unit is 5 cm finished. Every piece is a whole number of units, so every seam lines up with the grid.

Piece codes

The letter is the fabric (S sky, U sun gold, R red, W sail cloth, C copper, B brown, T teal, A aqua, N navy), the number the size. H are triangle units, Q quarter-circle units.

Appliqué

Quarter circles are fused to their background squares and stitched before any piecing. Their straight edges disappear into the seams; only the arcs are stitched.

Pressing

Press triangle seams toward the darker fabric and all other seams open. Press appliqué from the back.

Diagrams

All diagrams show the right side. Gaps show the order: the narrower the gap, the earlier the seam.

CUTTING

Cut each fabric


Each diagram is one strip cut across the width of the fabric, with the pieces in cutting order. Grey areas are left over. Squares with a dashed diagonal are for triangle units; squares with an arc are fabric for quarter circles, to be backed with fusible web and cut to shape later. Strips with a pale end are cut long on purpose and trimmed to fit.




Sky S

1.1m · background above the waterline


Cut 1 strip 26.5cm, 1 strip 16.5cm, 2 strips 11.5cm, 1 strip 8cm, 3 strips 6.5cm.




1 26.5cm strip → 1 × Q6 background square 26.5 × 26.5 · S12 at 33.5cm (2cm extra, trim to fit later), trimmed to 21.5cm wide · 2 × Q5 background squares 16.5 × 16.5 · 1 × Q4 background square 11.5 × 11.5



2 16.5cm strip → S11 at 16.5cm · S10 at 41.5cm, trimmed to 11.5cm wide · 2 × S9 at 11.5cm · 2 × Q4 background squares 11.5 × 11.5



3 11.5cm strip → 9 × Q4 background squares 11.5 × 11.5



4 11.5cm strip → 2 × S8 at 11.5cm · S6 at 36.5cm, trimmed to 6.5cm wide · S5 at 31.5cm, trimmed to 6.5cm wide · 2 × S2 at 6.5cm

	S7	S6
--	----	----

5 8cm strip → 1 square 8 × 8 for H2 · S7 at 58.5cm (2cm extra, trim to fit later), trimmed to 6.5cm wide · S6 at 38.5cm (2cm extra, trim to fit later), trimmed to 6.5cm wide

S4	S3	S3	S3	S3	S2
----	----	----	----	----	----

6 6.5cm strip → S4 at 26.5cm · 4 × S3 at 16.5cm · S2 at 11.5cm

S3	S3	S3	S3	Q2	Q2	Q2	Q2	Q3	Q3
----	----	----	----	----	----	----	----	----	----

7 6.5cm strip → 4 × S3 at 16.5cm · 4 × Q2 background squares 6.5 × 6.5 · 2 × Q3 background squares 6.5 × 6.5

S1	S1	S1	S1	S1	S1
----	----	----	----	----	----

8 6.5cm strip → 6 × S1 at 6.5cm

Piece list for sky

CODE	SIZE	QTY	USED IN
S1	6.5 × 6.5cm	6	section 1×6
S2	6.5 × 11.5cm	3	section 1×3
S3	6.5 × 16.5cm	8	section 1×8
S4	6.5 × 26.5cm	1	section 1
S5	6.5 × 31.5cm	1	section 1
S6	6.5 × 36.5cm	2	section 1×2
S7	6.5 × 56.5cm	1	section 1
S8	11.5 × 11.5cm	2	section 1×2
S9	11.5 × 16.5cm	2	section 1, section 2
S10	11.5 × 41.5cm	1	section 1
S11	16.5 × 16.5cm	1	section 2
S12	21.5 × 31.5cm	1	section 1
H2	8 × 8cm	1	squares for 1 triangle unit H2


CODE	SIZE	QTY	USED IN
Q2	6.5 × 6.5 cm	4	background squares, gull wing
Q3	6.5 × 6.5 cm	2	background squares, sail corner
Q4	11.5 × 11.5 cm	12	background squares, wave
Q5	16.5 × 16.5 cm	2	background squares, bow and stern
Q6	26.5 × 26.5 cm	1	background squares, rising sun

Sun gold U

1 fat quarter · sun

Cut 1 strip 27 cm.

Cutting from a fat quarter: cut the same strips along its long side instead of across the width of fabric.



1

27 cm strip → 1 square 27 × 27 for Q6 quarter circles

Piece list for sun gold

CODE	SIZE	QTY	USED IN
Q6	R 25cm	1	quarter circles, rising sun




Hanse red R


1 fat quarter · sail stripes, pennant, flag, sun

Cut 1 strip 12cm, 1 strip 8cm, 1 strip 6.5cm.

Cutting from a fat quarter: cut the same strips along its long side instead of across the width of fabric.



1 12cm strip → 1 square 12 × 12 for Q6 quarter circles · R3 at 36.5cm, trimmed to 6.5cm wide · R2 at 31.5cm, trimmed to 6.5cm wide



2 8cm strip → 1 square 8 × 8 for H2 · 2 squares 7 × 7 for Q3 quarter circles · 2 × R3 at 36.5cm, trimmed to 6.5cm wide



3 6.5cm strip → R2 at 31.5cm · 2 × R1 at 11.5cm

Piece list for hanse red

CODE	SIZE	QTY	USED IN
R1	6.5 × 11.5cm	2	section 1 × 2
R2	6.5 × 31.5cm	2	section 1 × 2
R3	6.5 × 36.5cm	3	section 1 × 3
H2	8 × 8cm	1	squares for 1 triangle unit H2
Q3	R 5cm	2	quarter circles, sail corner
Q6	R 10cm	1	quarter circles, rising sun



Sailcloth W

0.4m · sail stripes, flag, herring

Cut 1 strip 8cm, 2 strips 6.5cm.



1 8cm strip → 4 squares 8×8 for H1 · 8 squares 7×7 for Q1 quarter circles

W3	W3	W2	W1	W1	W1
----	----	----	----	----	----

2 6.5cm strip → 2 × W3 at 36.5cm · W2 at 11.5cm · 3 × W1 at 6.5cm

W3	W3	W2	W2	W1
----	----	----	----	----

3 6.5cm strip → 2 × W3 at 36.5cm · 2 × W2 at 11.5cm · W1 at 6.5cm

Piece list for sailcloth


CODE	SIZE	QTY	USED IN
W1	6.5×6.5 cm	4	section 7 × 4
W2	6.5×11.5 cm	3	section 1, section 6 × 2
W3	6.5×36.5 cm	4	section 1 × 4
H1	8×8 cm	4	squares for 8 triangle units H1
Q1	R 5cm	8	quarter circles, herring head



Copper C

0.5m · castles, planking, sun


Cut 1 strip 20 cm, 2 strips 6.5 cm.



- 1 20 cm strip → 1 square 20 × 20 for Q6 quarter circles · 2 squares 12 × 12 for Q5 quarter circles · 2 × C3 at 16.5 cm, trimmed to 6.5 cm wide · 2 × C2 at 11.5 cm, trimmed to 6.5 cm wide



- 2 6.5 cm strip → C5 at 61.5 cm · 2 × C4 at 21.5 cm



- 3 6.5 cm strip → 4 × C1 at 6.5 cm

Piece list for copper


CODE	SIZE	QTY	USED IN
C1	6.5 × 6.5 cm	4	section 1 × 4
C2	6.5 × 11.5 cm	2	section 1 × 2
C3	6.5 × 16.5 cm	2	section 1 × 2
C4	6.5 × 21.5 cm	2	section 1 × 2
C5	6.5 × 61.5 cm	1	section 2
Q5	R 10 cm	2	quarter circles, bow and stern
Q6	R 17.5 cm	1	quarter circles, rising sun



Oak brown B

0.4m · hull, mast, yard, rudder

Cut 1 strip 17 cm, 2 strips 6.5 cm.



- 1 17 cm strip → 2 squares 17×17 for Q5 quarter circles · 2 squares 7×7 for Q5 quarter circles · B2 at 11.5 cm, trimmed to 6.5 cm wide · 4 × B1 at 6.5 cm, trimmed to 6.5 cm wide



- 2 6.5 cm strip → B5 at 61.5 cm · B4 at 38.5 cm (2 cm extra, trim to fit later)




- 3 6.5 cm strip → B5 at 61.5 cm · 2 × B3 at 16.5 cm · B1 at 6.5 cm

Piece list for oak brown

CODE	SIZE	QTY	USED IN
B1	6.5×6.5 cm	5	section 1 × 5
B2	6.5×11.5 cm	1	section 1
B3	6.5×16.5 cm	2	section 1, section 2
B4	6.5×36.5 cm	1	section 1
B5	6.5×61.5 cm	2	section 2 × 2
Q5	R 15 cm	2	quarter circles, bow and stern
Q5	R 5 cm	2	quarter circles, bow and stern


 **Teal** T
0.5m · waves

Cut 2 strips 12 cm, 2 strips 6.5 cm.



1

12 cm strip → 8 squares 12 × 12 for Q4 quarter circles



2

12 cm strip → 4 squares 12 × 12 for Q4 quarter circles



3

6.5 cm strip → T1 at 63.5 cm (2 cm extra, trim to fit later)



4

6.5 cm strip → T1 at 61.5 cm

Piece list for teal

CODE	SIZE	QTY	USED IN
T1	6.5 × 61.5 cm	2	section 4 × 2
Q4	R 10 cm	12	quarter circles, wave




Aqua A

1 fat quarter · wave crests

Cut 1 strip 7cm.

Cutting from a fat quarter: cut the same strips along its long side instead of across the width of fabric.



1 7 cm strip → 12 squares 7 × 7 for Q4 quarter circles

Piece list for aqua

CODE	SIZE	QTY	USED IN
Q4	R 5cm	12	quarter circles, wave



Baltic navy N

1.1m · deep sea, gulls, binding

Cut 1 strip 21.5cm, 1 strip 11.5cm, 1 strip 8cm, 4 strips 6.5cm, 5 strips 6cm for the binding.



1 21.5cm strip → N7 at 53.5cm (2cm extra, trim to fit later) · N6 at 41.5cm, trimmed to 11.5cm wide



2 11.5cm strip → N5 at 31.5cm · N4 at 23.5cm (2cm extra, trim to fit later) · N4 at 21.5cm




3 8cm strip → 4 squares 8 × 8 for H1 · 4 squares 7 × 7 for Q2 quarter circles



4 6.5cm strip → N3 at 63.5cm (2cm extra, trim to fit later) · 6 × Q1 background squares 6.5 × 6.5



5 6.5cm strip → N3 at 63.5cm (2cm extra, trim to fit later) · N1 at 31.5cm · 1 × Q1 background square 6.5 × 6.5



6 6.5cm strip → N3 at 61.5cm



7 6.5cm strip → 2 × N2 at 46.5cm · 1 × Q1 background square 6.5 × 6.5


Piece list for baltic navy

CODE	SIZE	QTY	USED IN
N1	6.5 × 31.5 cm	1	section 7
N2	6.5 × 46.5 cm	2	section 7 × 2

CODE	SIZE	QTY	USED IN
N3	6.5 × 61.5 cm	3	section 5 ×2, section 7
N4	11.5 × 21.5 cm	2	section 6, section 7
N5	11.5 × 31.5 cm	1	section 6
N6	11.5 × 41.5 cm	1	section 6
N7	21.5 × 51.5 cm	1	section 7
H1	8 × 8 cm	4	squares for 8 triangle units H1
Q1	6.5 × 6.5 cm	8	background squares, herring head
Q2	R 5 cm	4	quarter circles, gull wing

STEP 1

Make the triangle units



The pale square is the wrong side of the lighter fabric. The drawn line is solid; the stitching lines are dashed.


1. Draw a diagonal on the wrong side of each lighter 8 cm square and place it right sides together on its darker partner.
2. Sew 0.75 cm from the line on both sides, cut on the line and press toward the darker fabric.
3. Trim each unit to 6.5×6.5 cm with the seam running exactly corner to corner.

- **H1**, sailcloth with Baltic navy: make 8 from 4 pairs of squares.
- **H2**, sky with Hanse red: make 1 from 1 pair of squares (one spare).

STEP 2

Make the quarter-circle units


29 units in 6 kinds. Every unit is a background square with one or more quarter discs fused into a corner. The discs are traced from the templates at the end of the pattern.




1 Trace on fusible web



2 Fuse, cut out




3 Fuse into the corner



4 Stitch along the arc

1. Trace each quarter circle onto the paper side of the fusible web. Mark the corner point on every tracing.
2. Iron the web onto the wrong side of the fabric squares cut for the discs and cut out on the line.
3. Peel the paper and lay the disc into the corner of its background square with both straight edges on the raw edges. Fuse.
4. For rings, fuse the next smaller disc into the same corner on top, then the next.
5. Stitch every arc 2 mm inside its edge with a straight stitch or a narrow zigzag, in matching thread. Leave the straight edges: the seams will hold them.

Keep it soft. Where three discs are stacked (sun, bow and stern), you may cut away the inside of the lower layers from the back, leaving about 1 cm under each arc.



Q1 • Herring head

MAKE 8 • 1 × 1 GRID UNIT

Background: Baltic navy square 6.5 × 6.5cm. Quarter circles, largest first: sailcloth R 5cm.



Q2 • Gull wing

MAKE 4 • 1 × 1 GRID UNIT

Background: sky square 6.5 × 6.5cm. Quarter circles, largest first: Baltic navy R 5cm.



Q3 • Sail corner

MAKE 2 • 1 × 1 GRID UNIT

Background: sky square 6.5 × 6.5cm. Quarter circles, largest first: Hanse red R 5cm.



Q4 • Wave

MAKE 12 • 2 ×
2 GRID UNITS

Background: sky square 11.5 × 11.5cm. Quarter circles, largest first: teal R 10cm, aqua R 5cm.



Q5 • Bow and stern

MAKE 2 • 3 ×
3 GRID UNITS

Background: sky square 16.5 × 16.5cm. Quarter circles, largest first: oak brown R 15cm, copper R 10cm, oak brown R 5cm.



Q6 • Rising sun


MAKE 1 • 5 ×
5 GRID UNITS

Background: sky square 26.5 × 26.5cm. Quarter circles, largest first: sun gold R 25cm, copper R 17.5cm, Hanse red R 10cm.

STEP 3

Piece the 7 sections

The top is pieced as 7 horizontal sections. Sew each one, press the seams open and check its size before going on: if it is more than 5 mm off, take in or let out a few of its seams (each seam changes the width by twice as much as you move it). Turn each triangle and quarter-circle unit exactly as its icon shows.



The sections. Thin lines are the seams inside each section.

In each diagram the pieces are spread apart along the seams you sew. Sections with columns are sewn column by column from the top down, then the columns are joined from left to right.

Icons show each unit as it sits in the quilt. For example  Q4 is a wave unit with its disc in the bottom right corner.



Long strips. Pieces with “trim to fit” in the cutting plan are a little long. Measure the part they join and trim them to match before sewing.

Section 1

1

Sky, rising sun, gulls, pennant, sail and both castles. Pieced in columns.

Measures 121.5 × 56.5 cm



Unit **2a**, left to right: Q2 Q2

Column **2**, top to bottom: S8 2a S10

Column **3**, top to bottom: S6 C4

Column **4**, top to bottom: S1 Q2 S2 B3 S1 C3

Unit **5a**, left to right: Q2 S1

Unit **5b**, left to right: C1 S1

Unit **5c**, left to right: B1 C1

Column **5**, top to bottom: S2 5a S8 W2 R1 S2 5b C2 5c C2

Column **6**, top to bottom: S3 B1 S3 C4

Column **7**, top to bottom: S3 B1 R2 Q3

Unit **8a**, left to right: S3 B1 R1 H2

Unit **8b**, left to right: S3 B1 S3

Unit **8c**, left to right: W3 R3 W3 R3 W3 R3 W3

Column **8**, top to bottom: S6 8a 8b B4 8c

Unit **9a**, left to right: **R2** **S5**

Unit **9b**, left to right: **Q3** **S1**

Column **9**, top to bottom: **S9** **B2** **9a** **9b**

Unit **10a**, left to right: **S4** **Q6**

Unit **10b**, left to right: **C1** **S1** **C1** **S3**

Unit **10c**, left to right: **C3** **S3**

Column **10**, top to bottom: **10a** **S12** **10b** **10c**

Join the columns left to right: **S7** **2** **3** **4** **5** **6** **7** **8** **9** **10**

S7, S6, B4 and S12 are cut 2cm longer than needed. Make the rest of the section first, then trim S7 to the height of column 2; S6 to the width of unit 8a; B4 to the width of unit 8c; S12 to the width of unit 10b before you join them.



Pin points: 1 with section 2 ▲

Section 2

2

The hull: the two curved ends, the rudder and three long plank strips.

Measures 121.5 × 16.5 cm



Column **4**, top to bottom: **B5** **C5** **B5**

Join the columns left to right: **S9** **B3** **Q5** **4** **Q5** **S11**

Pin points: 1 with section 1 ▼


Arc ends to match: 4. Where a ring of Q5 meets a seam or another ring, pin it like a seam crossing.

Section 3

3

Twelve wave units in a row, turned alternately.

Measures 121.5 × 11.5 cm



Join left to right:




Arc ends to match: 6. Where a ring of Q4 meets a seam or another ring, pin it like a seam crossing.

Section 4

4

The teal band under the waves.

Measures 121.5 × 6.5 cm



Join left to right: T1 T1


T1 is cut 2cm longer than needed: trim the joined strip to the width of the section above.

Section 5

5

A navy band.

Measures 121.5 × 6.5 cm



Join left to right: N3 N3



N3 is cut 2cm longer than needed: trim the joined strip to the width of the section above.

Section 6

6

Two herring swimming with the ship.

Measures 121.5 × 11.5 cm



Column 2, top to bottom: H1 H1

Column 4, top to bottom: Q1 Q1

Column 6, top to bottom: H1 H1

Column 8, top to bottom: Q1 Q1


Join the columns left to right: 2 4 6 8

Section 7

7

Two more herring and the bottom of the sea.

Measures 121.5 × 21.5 cm



Unit 2a, left to right: H1 W1 Q1 N2

Unit 2b, left to right: H1 W1 Q1 N1 H1 W1 Q1

Unit 2c, left to right: N2 H1 W1 Q1


Column 2, top to bottom: 2a 2b 2c N3

Join the columns left to right: N7 2 N4

N7, N3 and N4 are cut 2cm longer than needed. Make the rest of the section first, then trim N7 to the height of column 2; N3 to the width of unit 2c; N4 to the height of column 2 before you join them.

STEP 4

Join the sections



Join the sections from top to bottom.

1. Join sections 4 and 5 first: sew each pair of strips end to end and trim the band to the width of section 3.
2. Join sections 1 to 7 from top to bottom. Pin at the ends and at every seam that meets a seam across the join, then ease in any difference between pins.
3. The quilt top measures 121.5 × 121.5 cm. Stay-stitch around the edge about 0.3 cm from the raw edge.

Quilt, bind and hang

Quilting

1. Layer backing (right side down), batting and top, and baste.
2. Stitch in the ditch around the ship and along the waterline.
3. **Sky:** straight horizontal lines 2.5 cm apart, broken by echo arcs that ripple out from the sun.
4. **Sea:** gently wavy lines 1.7 cm apart in the navy, flowing round the herring.
5. **Appliqué:** echo each arc once, a few millimetres inside the stitching.

Binding and sleeve

1. Trim batting and backing even with the top.
2. Join the navy binding strips with diagonal seams and press in half lengthwise.
3. Hem the sleeve ends, fold it lengthwise and baste it to the top edge of the back so the binding seam catches it.
4. Sew the binding on with a 0.75 cm seam, mitring the corners, and hand-stitch it to the back. Hand-stitch the lower edge of the sleeve.
5. Add a label: your name, the year, and “Kogge”.




--- Suggested quilting lines


Quarter-circle templates

Print this page at 100 % (“actual size”) and check the test square with a ruler before you trace. Each template is a quarter circle around the corner of the finished unit; its straight edges include the seam allowance, so they go on the raw edges of the background square. The dashed lines are the seam lines.


The two largest arcs do not fit on a sheet: R 17.5 cm for Q6 copper; R 25 cm for Q6 sun gold. Draw them with a string compass: pin a strip of paper to the fusible web at the corner point 0.75 cm in from both edges, mark the radius on the strip, and swing a pencil through the hole.




Test square: must measure 5 × 5 cm



R 5 cm · Q1 sailcloth, Q2 Baltic navy, Q3 Hanse red, Q4 aqua, Q5 oak brown



R 10 cm · Q4 teal, Q5 copper, Q6 Hanse red



R 15 cm · Q5 oak brown

Layout chart

The whole quilt with every piece code. Brackets mark the sections. Triangle and quarter-circle units carry their codes in the section steps.



Kogge is an original quilt design, inspired by the modular geometric illustrations of Siggi Eggertsson and by the Bremen cog of about 1380. Every measurement, cutting plan and diagram on this page is generated from one design grid and checked against it, and the top was also sewn in software with real seam allowances.