

Kogge

A Hanseatic cog in squares, triangles and quarter circles

The cog was the ship of the Hanseatic League, the league of merchant towns led by Lübeck that dominated trade on the Baltic and the North Sea from the 13th to the 15th century. The best-preserved cog ever found was built around 1380 and found in the river Weser at Bremen in 1962. The quilt's style is inspired by the modular geometric illustrations of the Icelandic artist Siggí Eggertsson: every square of a grid holds one simple shape, and quarter circles turn hard pixels into a round hull, rolling waves and a rising sun.

FINISHED SIZE

120 × 120 cm

GRID

24 × 24 squares of 5 cm

PIECES

82 patches, plus squares for 9 triangle units and 29 quarter-circle units

FABRICS


9: sky and navy by the metre,
the rest in small cuts

LEVEL

Intermediate

TECHNIQUES

Rotary cutting, half-square triangles, fusible appliqué, straight-seam piecing




Four shapes, one grid

Each square of the 24×24 grid holds a square of one fabric, a half-square triangle, or part of a quarter circle. Stacking smaller quarter circles on bigger ones gives the rings that bend the copper plank band round the bow and stern, curl the waves and colour the rising sun.

The cog. One mast and one square sail, castles fore and aft, and a rudder hung on the sternpost. Cogs were among the first northern ships to steer that way instead of with an oar over the side.

The flag. White over red is the flag of Lübeck, the leading city of the League. Red and white are still the colours of the old Hanseatic towns.

The herring. Baltic herring, preserved with salt from Lüneburg, was one of the trades that made the Hanse rich, so a shoal swims along with the ship.



The modules. A quarter circle is a background square with a quarter disc appliquéd into one corner; rings are smaller discs stacked on top.

What you need

MATERIAL	AMOUNT	USED FOR
 Sky S	1.1m	Background above the waterline
 Sun gold U	1 fat quarter 50 × 55 cm	Sun
 Hanse red R	1 fat quarter 50 × 55 cm	Sail stripes, pennant, flag, sun
 Sailcloth W	0.4m	Sail stripes, flag, herring
 Copper C	0.5m	Castles, planking, sun
 Oak brown B	0.4m	Hull, mast, yard, rudder
 Teal T	0.5m	Waves
 Aqua A	1 fat quarter 50 × 55 cm	Wave crests
 Baltic navy N	1.2m	Deep sea, gulls, binding
Backing	2.8 m or 1.4 m of extra-wide backing	Cut two lengths of 140 cm, join them side by side and trim to 135 × 135 cm
Batting	135 × 135 cm	Thin cotton keeps a wall quilt flat
Fusible web	1.5 m, 45 cm wide	Lightweight, sew-through and paper-backed; for the quarter discs
Hanging sleeve	22 × 115 cm	Leftover backing works
Thread	Grey cotton, 50 wt	Plus thread to match each appliqué colour

Fabric choice. Solids or tone-on-tone prints keep the shapes crisp. Check that the sky, the sailcloth and the aqua read clearly apart, and that the navy is the darkest fabric.

Tools: rotary cutter, cutting mat and a long ruler; a square ruler of 16.5 cm or more for trimming the triangle units; pins; small sharp scissors for the appliqué; an iron, a pressing cloth and an appliqué pressing sheet or baking paper; a pencil; clear tape for joining template parts; a walking foot for straight-line quilting and an open-toe foot for stitching the arcs.

How this pattern works

Read first

Read the whole pattern before you cut. Cut every fabric as its cutting plan shows and label each stack with its code as you go.

Abbreviations

WOF: width of fabric, from selvage to selvage (105 cm usable assumed). RST: right sides together. HST: half-square triangle. FQ: fat quarter (50 × 55 cm).

Prewashing

Optional. The fabric amounts allow for 5% shrinkage.

Seam allowance

Sew all seams right sides together. All sizes include 0.75 cm seams. Sew six 6.5 cm scrap squares into a row: it must be 31.5 cm long, give or take 2 mm. If it is shorter your seams are too wide, if longer too narrow: adjust and sew a new row. It matters: with every seam 1 mm too wide, section 1 comes out 2.2cm narrower than the hull below it.

Grid

One grid square is 5 cm finished. Every piece covers whole grid squares, so every seam lines up with the grid.

Sizes

Every “measures” size is raw edge to raw edge, seam allowances included. Metric and imperial are separate plans on a 5 cm grid: use one system throughout.

Piece codes

The letter is the fabric (S sky, U sun gold, R Hanse red, W sailcloth, C copper, B oak brown, T teal, A aqua, N Baltic navy); the number ranks that fabric's pieces by size. A + marks a piece cut long on purpose (see Terms). H1 and H2 are triangle units, Q1 to Q6 quarter-circle units.

Terms

Quarter-circle unit: a background square with quarter discs fused into one corner. *Ring*: a smaller disc fused on a larger one. *Segment*: a few pieces sewn together first, inside a column. *Pin point*: where a seam or an outline must meet its partner across a join. *Trim to fit*: pieces marked + are cut 2 cm long and trimmed to the part they join.

Appliqué

Quarter discs are fused to their background squares and stitched before any piecing. Their straight edges disappear into the seams; only the curved edges are stitched.

Pressing

Press triangle seams toward the darker fabric and all other seams open. Press appliqué from the back.

Diagrams

All diagrams show the right side unless noted. Pieces are drawn apart along the seams you sew: the closer two pieces are drawn, the earlier you sew them.

CUTTING

Cut each fabric


Each diagram is one strip cut across the width of fabric (WOF), with its pieces in cutting order; grey areas are left over. Squares with a dashed diagonal are for triangle units. Squares with an arc are fabric for quarter discs, backed with fusible web and cut to shape later. A pale end or edge marks a piece cut long on purpose (+). The plans assume 105 cm of usable width; if your fabric is narrower, cut a piece that no longer fits from an extra strip of the same width.




Sky S

1.1m · background above the waterline


Cut strips across the width of fabric (WOF): 1 × 26.5cm, 1 × 16.5cm, 2 × 11.5cm, 1 × 8cm, 3 × 6.5cm.



- 1 Cut a strip 26.5cm × WOF. From it cut:
 - 1 square 26.5 × 26.5cm · Q6 background
 - 1 rectangle 21.5 × 33.5cm · S12+, 2cm long on purpose: trim to fit later
 - 2 squares 16.5 × 16.5cm · Q5 backgrounds
 - 1 square 11.5 × 11.5cm · Q4 background



- 2 Cut a strip 16.5cm × WOF. From it cut:
 - 1 square 16.5 × 16.5cm · S11
 - 1 rectangle 11.5 × 41.5cm · S10
 - 2 rectangles 11.5 × 16.5cm · S9
 - 2 squares 11.5 × 11.5cm · Q4 backgrounds



- 3 Cut a strip 11.5cm × WOF. From it cut:
 - 9 squares 11.5 × 11.5cm · Q4 backgrounds

S8	S8	S6	S5	S2	S2

4 Cut a strip 11.5cm × WOF. From it cut:

- 2 squares 11.5 × 11.5cm · S8
- 1 rectangle 6.5 × 36.5cm · S6
- 1 rectangle 6.5 × 31.5cm · S5
- 2 rectangles 6.5 × 11.5cm · S2

	S7+	S6+
--	-----	-----

5 Cut a strip 8cm × WOF. From it cut:

- 1 square 8 × 8cm · for triangle units H2
- 1 rectangle 6.5 × 58.5cm · S7+, 2cm long on purpose: trim to fit later
- 1 rectangle 6.5 × 38.5cm · S6+, 2cm long on purpose: trim to fit later

S4	S3	S3	S3	S3	S2
----	----	----	----	----	----

6 Cut a strip 6.5cm × WOF. From it cut:

- 1 rectangle 6.5 × 26.5cm · S4
- 4 rectangles 6.5 × 16.5cm · S3
- 1 rectangle 6.5 × 11.5cm · S2

S3	S3	S3	S3	Q2	Q2	Q2	Q2	Q3	Q3
----	----	----	----	----	----	----	----	----	----

7 Cut a strip 6.5cm × WOF. From it cut:

- 4 rectangles 6.5 × 16.5cm · S3
- 4 squares 6.5 × 6.5cm · Q2 backgrounds
- 2 squares 6.5 × 6.5cm · Q3 backgrounds

S1	S1	S1	S1	S1	S1				
----	----	----	----	----	----	--	--	--	--

8 Cut a strip 6.5cm × WOF. From it cut:

- 6 squares 6.5 × 6.5cm · S1

Piece list for sky

CODE	SIZE	QTY	USED IN
S1	6.5 × 6.5cm	6	section 1×6
S2	6.5 × 11.5cm	3	section 1×3
S3	6.5 × 16.5cm	8	section 1×8

CODE	SIZE	QTY	USED IN
S4	6.5 × 26.5cm	1	section 1
S5	6.5 × 31.5cm	1	section 1
S6	6.5 × 36.5cm	1	section 1
S6+	6.5 × 38.5cm	1	section 1; cut long, trim to fit
S7+	6.5 × 58.5cm	1	section 1; cut long, trim to fit
S8	11.5 × 11.5cm	2	section 1 × 2
S9	11.5 × 16.5cm	2	section 1, section 2
S10	11.5 × 41.5cm	1	section 1
S11	16.5 × 16.5cm	1	section 2
S12+	21.5 × 33.5cm	1	section 1; cut long, trim to fit
H2	8 × 8cm	1	square for 1 triangle unit H2
Q2	6.5 × 6.5cm	4	background squares, gull wing
Q3	6.5 × 6.5cm	2	background squares, sail corner
Q4	11.5 × 11.5cm	12	background squares, wave
Q5	16.5 × 16.5cm	2	background squares, bow and stern
Q6	26.5 × 26.5cm	1	background squares, rising sun

Sun gold

U

1 fat quarter · sun

Cut strips along the long side of the fat quarter: 1 × 27 cm.



1

Cut a strip 27 cm along the long side of the fat quarter. From it cut:

- 1 square 27 × 27 cm · for template 5 (Q6)

Piece list for sun gold

CODE	SIZE	QTY	USED IN
Q6	radius 25 cm	1	template 5, rising sun

Hanse red

R

1 fat quarter · sail stripes, pennant, flag, sun


Cut strips along the long side of the fat quarter: 1 × 12 cm, 5 × 6.5 cm.



1

Cut a strip 12 cm along the long side of the fat quarter. From it cut:

- 1 square 12 × 12 cm · for template 2 (Q6)
- 1 square 8 × 8 cm · for triangle units H2
- 2 squares 7 × 7 cm · for template 1 (Q3)



2

Cut a strip 6.5 cm along the long side of the fat quarter. From it cut:


- 1 rectangle 6.5 × 36.5 cm · R3



3

Cut a strip 6.5 cm along the long side of the fat quarter. From it cut:

- 1 rectangle 6.5 × 36.5 cm · R3
- 1 rectangle 6.5 × 11.5 cm · R1



- 4 Cut a strip 6.5cm along the long side of the fat quarter. From it cut:
- 1 rectangle 6.5 × 36.5cm · R3
 - 1 rectangle 6.5 × 11.5cm · R1



- 5 Cut a strip 6.5cm along the long side of the fat quarter. From it cut:
- 1 rectangle 6.5 × 31.5cm · R2



- 6 Cut a strip 6.5cm along the long side of the fat quarter. From it cut:
- 1 rectangle 6.5 × 31.5cm · R2

Piece list for Hanse red

CODE	SIZE	QTY	USED IN
R1	6.5 × 11.5cm	2	section 1 × 2
R2	6.5 × 31.5cm	2	section 1 × 2
R3	6.5 × 36.5cm	3	section 1 × 3
H2	8 × 8cm	1	square for 1 triangle unit H2
Q3	radius 5cm	2	template 1, sail corner
Q6	radius 10cm	1	template 2, rising sun



Sailcloth W

0.4m · sail stripes, flag, herring

Cut strips across the width of fabric (WOF): 1 × 8cm, 2 × 6.5cm.



- 1 Cut a strip 8cm × WOF. From it cut:
- 4 squares 8 × 8cm · for triangle units H1
 - 8 squares 7 × 7cm · for template 1 (Q1)

W3	W3	W2	W2	W1	
----	----	----	----	----	--

2 Cut a strip 6.5cm × WOF. From it cut:

- 2 rectangles 6.5 × 36.5cm · W3
- 2 rectangles 6.5 × 11.5cm · W2
- 1 square 6.5 × 6.5cm · W1

W3	W3	W2	W1	W1	W1
----	----	----	----	----	----

3 Cut a strip 6.5cm × WOF. From it cut:

- 2 rectangles 6.5 × 36.5cm · W3
- 1 rectangle 6.5 × 11.5cm · W2
- 3 squares 6.5 × 6.5cm · W1

Piece list for sailcloth

CODE	SIZE	QTY	USED IN
W1	6.5 × 6.5 cm	4	section 7 ×4
W2	6.5 × 11.5 cm	3	section 1, section 6 ×2
W3	6.5 × 36.5 cm	4	section 1×4
H1	8 × 8 cm	4	squares for 8 triangle units H1
Q1	radius 5 cm	8	template 1, herring head

Copper C

0.5m · castles, planking, sun

Cut strips across the width of fabric (WOF): 1 × 20 cm, 2 × 6.5 cm.

			C3	C3	C2	C2
---	---	---	----	----	----	----

1 Cut a strip 20 cm × WOF. From it cut:

- 1 square 20 × 20 cm · for template 4 (Q6)
- 2 squares 12 × 12 cm · for template 2 (Q5)
- 2 rectangles 6.5 × 16.5 cm · C3
- 2 rectangles 6.5 × 11.5 cm · C2

C5

C4

C4

2

Cut a strip 6.5cm × WOF. From it cut:

• 1 rectangle 6.5 × 61.5cm · C5

• 2 rectangles 6.5 × 21.5cm · C4

C1

C1

C1

C1

3

Cut a strip 6.5cm × WOF. From it cut:

• 4 squares 6.5 × 6.5cm · C1

Piece list for copper

CODE	SIZE	QTY	USED IN
C1	6.5 × 6.5cm	4	section 1×4
C2	6.5 × 11.5cm	2	section 1×2
C3	6.5 × 16.5cm	2	section 1×2
C4	6.5 × 21.5cm	2	section 1×2
C5	6.5 × 61.5cm	1	section 2
Q5	radius 10cm	2	template 2, bow and stern
Q6	radius 17.5cm	1	template 4, rising sun

Oak brown

B

0.4m · hull, mast, yard, rudder

Cut strips across the width of fabric (WOF): 1 × 17cm, 2 × 6.5cm.

B2

B1

B1

B1

B1

1

Cut a strip 17cm × WOF. From it cut:

• 2 squares 17 × 17cm · for template 3 (Q5)

• 2 squares 7 × 7cm · for template 1 (Q5)

• 1 rectangle 6.5 × 11.5cm · B2

• 4 squares 6.5 × 6.5cm · B1

B5

B4+

2

Cut a strip 6.5cm × WOF. From it cut:

- 1 rectangle 6.5 × 61.5cm · B5
- 1 rectangle 6.5 × 38.5cm · B4+, 2cm long on purpose: trim to fit later

B5

B3

B3

B1

3

Cut a strip 6.5cm × WOF. From it cut:

- 1 rectangle 6.5 × 61.5cm · B5
- 2 rectangles 6.5 × 16.5cm · B3
- 1 square 6.5 × 6.5cm · B1


Piece list for oak brown

CODE	SIZE	QTY	USED IN
B1	6.5 × 6.5cm	5	section 1×5
B2	6.5 × 11.5cm	1	section 1
B3	6.5 × 16.5cm	2	section 1, section 2
B4+	6.5 × 38.5cm	1	section 1; cut long, trim to fit
B5	6.5 × 61.5cm	2	section 2 ×2
Q5	radius 15 cm	2	template 3, bow and stern
Q5	radius 5 cm	2	template 1, bow and stern

Teal T

0.5m · waves


Cut strips across the width of fabric (WOF): 2 × 12cm, 2 × 6.5cm.



1

Cut a strip 12cm × WOF. From it cut:

- 8 squares 12 × 12cm · for template 2 (Q4)



- 2 Cut a strip 12cm × WOF. From it cut:
- 4 squares 12 × 12cm · for template 2 (Q4)



- 3 Cut a strip 6.5cm × WOF. From it cut:
- 1 rectangle 6.5 × 63.5cm · T1+, 2cm long on purpose: trim to fit later



- 4 Cut a strip 6.5cm × WOF. From it cut:
- 1 rectangle 6.5 × 61.5cm · T1

Piece list for teal

CODE	SIZE	QTY	USED IN
T1	6.5 × 61.5cm	1	section 4
T1+	6.5 × 63.5cm	1	section 4; cut long, trim to fit
Q4	radius 10cm	12	template 2, wave



Aqua A

1 fat quarter · wave crests

Cut strips along the long side of the fat quarter: 2 × 7cm.



- 1 Cut a strip 7cm along the long side of the fat quarter. From it cut:
- 7 squares 7 × 7cm · for template 1 (Q4)



- 2 Cut a strip 7cm along the long side of the fat quarter. From it cut:
- 5 squares 7 × 7cm · for template 1 (Q4)

Piece list for aqua

CODE	SIZE	QTY	USED IN
Q4	radius 5 cm	12	template 1, wave

Baltic navy

N

1.2m · deep sea, gulls, binding

Cut strips across the width of fabric (WOF): 1 × 23.5 cm, 1 × 11.5 cm, 1 × 8 cm, 4 × 6.5 cm, plus 6 × 6 cm for the binding.

N7+

N6

N4+

1

Cut a strip 23.5 cm × WOF. From it cut:

• 1 rectangle 23.5 × 51.5 cm · N7+, 2 cm long on purpose: trim to fit later

• 1 rectangle 11.5 × 41.5 cm · N6

• 1 rectangle 11.5 × 23.5 cm · N4+, 2 cm long on purpose: trim to fit later

N5

N4

N2

2

Cut a strip 11.5 cm × WOF. From it cut:

• 1 rectangle 11.5 × 31.5 cm · N5

• 1 rectangle 11.5 × 21.5 cm · N4

• 1 rectangle 6.5 × 46.5 cm · N2

3

Cut a strip 8 cm × WOF. From it cut:

• 4 squares 8 × 8 cm · for triangle units H1

• 4 squares 7 × 7 cm · for template 1 (Q2)

N3+

Q1

Q1

Q1

Q1

Q1

Q1

4

Cut a strip 6.5 cm × WOF. From it cut:

• 1 rectangle 6.5 × 63.5 cm · N3+, 2 cm long on purpose: trim to fit later

• 6 squares 6.5 × 6.5 cm · Q1 backgrounds

Kogge · Hanseatic cog patchwork quilt · version 1.1, October 2026

15 / 40

N3+

N1

Q1

5 Cut a strip 6.5cm × WOF. From it cut:

- 1 rectangle 6.5 × 63.5cm · N3+, 2cm long on purpose: trim to fit later
- 1 rectangle 6.5 × 31.5cm · N1
- 1 square 6.5 × 6.5cm · Q1 background

N3

Q1

6 Cut a strip 6.5cm × WOF. From it cut:

- 1 rectangle 6.5 × 61.5cm · N3
- 1 square 6.5 × 6.5cm · Q1 background

N2

7 Cut a strip 6.5cm × WOF. From it cut:


- 1 rectangle 6.5 × 46.5cm · N2

Piece list for Baltic navy

CODE	SIZE	QTY	USED IN
N1	6.5 × 31.5 cm	1	section 7
N2	6.5 × 46.5 cm	2	section 7 × 2
N3	6.5 × 61.5 cm	1	section 5
N3+	6.5 × 63.5 cm	2	section 5, section 7; cut long, trim to fit
N4	11.5 × 21.5 cm	1	section 6
N4+	11.5 × 23.5 cm	1	section 7; cut long, trim to fit
N5	11.5 × 31.5 cm	1	section 6
N6	11.5 × 41.5 cm	1	section 6
N7+	23.5 × 51.5 cm	1	section 7; cut long, trim to fit
H1	8 × 8 cm	4	squares for 8 triangle units H1
Q1	6.5 × 6.5 cm	8	background squares, herring head
Q2	radius 5 cm	4	template 1, gull wing

STEP 1

Make the triangle units



The pale square is the wrong side of the lighter fabric. The drawn line is solid; the stitching lines are dashed.

1. Draw a diagonal on the wrong side of each lighter 8 cm square and place it right sides together on its darker partner.
2. Sew 0.75 cm from the line on both sides, cut on the line and press toward the darker fabric.
3. Trim each unit to 6.5×6.5 cm with the seam running exactly corner to corner: lay the 45° line of the square ruler on the seam, trim two sides, turn the unit and trim the other two.


- **H1**, sailcloth with Baltic navy: make 8 from 4 pairs of squares.
- **H2**, sky with Hanse red: make 1 from 1 pair of squares (one spare).

STEP 2

Make the quarter-circle units

Make 29 quarter-circle units of 6 kinds (Q1 to Q6). Every unit is a background square with one or more quarter discs fused into a corner. The discs are traced from 5 templates at the end of the pattern; this list says how many of each to trace, and for which fabric.


TEMPLATE	RADIUS	TRACE	FABRIC (UNIT)
Template 1	5cm	28	8 sailcloth (Q1), 4 Baltic navy (Q2), 2 Hanse red (Q3), 12 aqua (Q4), 2 oak brown (Q5)
Template 2	10cm	15	12 teal (Q4), 2 copper (Q5), 1 Hanse red (Q6)
Template 3	15cm	2	2 oak brown (Q5)
Template 4	17.5cm	1	1 copper (Q6)
Template 5	25cm	1	1 sun gold (Q6)




1 Trace on fusible web



2 Fuse, cut out



3 Fuse into the corner




4 Stitch along the arc

- Trace.** Lay the fusible web paper side up over a template and trace it as many times as the list says, about 1 cm apart. Mark the corner dot and write the unit code beside each tracing. Quarter circles are symmetrical, so they never need reversing.
- Rough-cut.** Cut each tracing out about 5 mm outside the line. On templates 3 to 5, also cut away the middle, leaving a ring of web about 1.5 cm wide inside the line, so the sun, bow and stern stay soft.
- Fuse.** Iron each tracing, paper side up, onto the wrong side of its fabric square, with its straight edges along two edges of the square. Follow the instructions of your web.
- Cut.** Cut along the curved line with small sharp scissors. With the paper still on, the fabric cuts like card.
- Place.** Let the fabric cool, then peel off the paper. Lay the disc right side up in the corner of its background square, as the unit picture shows: corner dot on the corner, both straight edges on the raw edges. Fuse with a pressing cloth.
- Rings.** Fuse the next smaller disc into the same corner on top of it, then the next.

7. **Stitch.** Stitch along every arc about 2 mm inside its edge in matching thread, with an open-toe foot: a straight stitch, a narrow zigzag (1.5 mm wide and long) or a blanket stitch. Zigzag and blanket stitch keep raw edges tidiest in the wash. Leave the straight edges: the seams hold them.
8. **Check.** Press from the back. Trim anything that overhangs the square; the unit still measures its cut size.


New to fusible appliqué? Make one herring head (Q1) from scraps first, to learn how hot and how long your web needs, and how your machine stitches round a curve.



Q1 • Herring head

MAKE 8 • 6.5 ×
6.5 CM SQUARE


Background: Baltic navy square 6.5 × 6.5 cm. Discs, largest first: template 1 in sailcloth. The finished unit still measures 6.5 × 6.5 cm.



Q2 • Gull wing

MAKE 4 • 6.5 ×
6.5 CM SQUARE


Background: sky square 6.5 × 6.5 cm. Discs, largest first: template 1 in Baltic navy. The finished unit still measures 6.5 × 6.5 cm.



Q3 • Sail corner

MAKE 2 • 6.5 ×
6.5 CM SQUARE


Background: sky square 6.5 × 6.5 cm. Discs, largest first: template 1 in Hanse red. The finished unit still measures 6.5 × 6.5 cm.



Q4 • Wave

MAKE 12 • 11.5 ×
11.5 CM SQUARE


Background: sky square 11.5 × 11.5 cm. Discs, largest first: template 2 in teal, template 1 in aqua. The finished unit still measures 11.5 × 11.5 cm.



Q5 • Bow and stern

MAKE 2 • 16.5 ×
16.5 CM SQUARE

Background: sky square 16.5 × 16.5 cm. Discs, largest first: template 3 in oak brown, template 2 in copper, template 1 in oak brown. The finished unit still measures 16.5 × 16.5 cm.



Q6 • Rising sun


MAKE 1 • 26.5 ×
26.5 CM SQUARE

Background: sky square 26.5 × 26.5 cm. Discs, largest first: template 5 in sun gold, template 4 in copper, template 2 in Hanse red. The finished unit still measures 26.5 × 26.5 cm.

STEP 3

Piece the 7 sections

The top is pieced as 7 horizontal sections. Sew each one, press the seams open and check its size before going on: if it is more than 5 mm off, take in or let out a few of its seams (each seam changes the width by twice as much as you move it). Turn each triangle and quarter-circle unit exactly as its icon shows. A single piece that fills a whole column is shown by its code alone.




The sections. Thin lines are the seams inside each section.

In each diagram the pieces are spread apart along the seams you sew. Sections with columns are sewn column by column from the top down, then the columns are joined from left to right.

Icons show each unit as it sits in the quilt. For example  Q4 is a wave unit with its disc in the bottom right corner.

Trim to fit. Pieces marked + are cut a little long. Each section says what to trim them to, before you sew them on.

Sky, rising sun, gulls, pennant, sail
and both castles. Pieced in
columns.



Column **2**, top to bottom: **S8** **2a** **S10** measures 11.5 × 56.5 cm

Column 4, top to bottom: S1  Q2 S2 B3 S1 C3 measures 6.5 × 56.5 cm

Column 5, top to bottom: S2 5a S8 W2 R1 S2 5b C2 5c C2

measures 11.5 × 56.5 cm

Column **7**, top to bottom: **S3** **B1** **R2** **Q3** measures 6.5 × 56.5 cm

Segment **8c**, left to right: **W3** **R3** **W3** **R3** **W3** **R3** **W3** measures 36.5 × 36.5 cm

Column **8**, top to bottom: **S6+** **8a** **8b** **B4+** **8c** measures 36.5 × 56.5 cm

Segment **9a**, left to right: **R2** **S5** measures 11.5 × 31.5 cm

Segment **9b**, left to right: **Q3** **S1** measures 11.5 × 6.5 cm

Column **9**, top to bottom: **S9** **B2** **9a** **9b** measures 11.5 × 56.5 cm

Segment **10a**, left to right: **S4** **Q6** measures 31.5 × 26.5 cm

Segment **10b**, left to right: **C1** **S1** **C1** **S3** measures 31.5 × 6.5 cm

Segment **10c**, left to right: **C3** **S3** measures 31.5 × 6.5 cm

Column **10**, top to bottom: **10a** **S12+** **10b** **10c** measures 31.5 × 56.5 cm

Join the columns left to right: **S7+** **2** **3** **4** **5** **6** **7** **8** **9** **10** and press the seams open

S7+, S6+, B4+ and S12+ are cut 2 cm longer than needed. Make the rest of the section first, then trim S7+ to the height of column 2; S6+ to the width of segment 8a; B4+ to the width of segment 8c; S12+ to the width of segment 10b before you join them.



Pin points to match when you join the sections: 1 point with section 2, marked ▲ below the diagram.

Section 2

2

The hull: the two curved ends, the rudder and three long plank strips.

Measures 121.5 × 16.5 cm



Column **4**, top to bottom: **B5** **C5** **B5** measures 61.5 × 16.5 cm

Join the columns left to right: **S9** **B3** **Q5** **4** **Q5** **S11** and press the seams open

Pin points to match when you join the sections: 1 point with section 1, marked ▼ above the diagram.


Ring ends to match: 4, marked ● on the diagram, where a ring of Q5 meets a seam or another ring. Pin them like seam crossings.

3

Section 3

12 wave units (Q4) in a row, turned alternately.

Measures 121.5 × 11.5 cm



Join left to right:



and press the seams open


Ring ends to match: 6, marked ● on the diagram, where a ring of Q4 meets a seam or another ring. Pin them like seam crossings.

4

Section 4

The teal band under the waves.

Measures 121.5 × 6.5 cm



Join left to right: **T1** **T1+** and press the seams open


T1+ is cut 2cm longer than needed: trim the joined strip to the width of the section above.

5

Section 5

A navy band.

Measures 121.5 × 6.5 cm



Join left to right: **N3** **N3+** and press the seams open



N3+ is cut 2cm longer than needed: trim the joined strip to the width of the section above.

Section 6

6

Two herring swimming with the ship.

Measures 121.5 × 11.5 cm



Column **2**, top to bottom:   measures 6.5 × 11.5 cm

Column **4**, top to bottom:   measures 6.5 × 11.5 cm

Column **6**, top to bottom:   measures 6.5 × 11.5 cm

Column **8**, top to bottom:   measures 6.5 × 11.5 cm



Join the columns left to right: **N4** **2** **W2** **4** **N6** **6** **W2** **8** **N5** and press the seams open

Section 7

7

Two more herring and the bottom of the sea.

Measures 121.5 × 21.5 cm



Segment **2a**, left to right: measures 61.5 × 6.5 cm

Segment **2b**, left to right: measures 61.5 × 6.5 cm

Segment **2c**, left to right: measures 61.5 × 6.5 cm


Column **2**, top to bottom: measures 61.5 × 21.5 cm

Join the columns left to right: and press the seams open

N7+, N3+ and N4+ are cut 2cm longer than needed. Make the rest of the section first, then trim N7+ to the height of column 2; N3+ to the width of segment 2c; N4+ to the height of column 2 before you join them.

STEP 4

Join the sections



Join the sections from top to bottom.

1. Check that sections 4 and 5 are trimmed to the width of section 3, as their notes say.
2. Join sections 1 to 7 from top to bottom. Pin at the ends and at every seam that meets a seam across the join, then ease in any difference between pins.
3. The quilt top measures 121.5 × 121.5 cm. Stay-stitch around the edge about 0.3 cm from the raw edge.


Quilt, bind and hang

Step 5 • Quilting


1. Layer backing (right side down), batting and top, and baste.
2. **Outlines first:** quilt round the ship, the sun, the gulls, the tops of the waves and each herring, about 2 mm outside each shape (the seams are pressed open, so there is no ditch to sink into). This holds the layers before the long lines.
3. **Sky:** straight horizontal lines 2.5 cm apart, carried across the castles and broken by echo arcs that ripple out from the sun.
4. **Sail:** vertical lines 2.5 cm apart, 2 mm beside every stripe seam and down the middle of each stripe. Quilt the flag the same way, beside the seam between its white and red halves.
5. **Hull:** one line along the middle of each plank, curving round the bow and stern with the rings. One line down the mast, the yard, the flagpole and the rudder.
6. **Sun and waves:** one line in the middle of every ring (two in the wide rings of the sun), and one along the teal band.
7. **Sea:** gently wavy lines 1.7 cm apart in the navy, stopping at the herring. Give each herring a spine from tail to head and a gill line.
8. No two lines are more than 8 cm apart. Check the maximum quilting distance on your batting's packet.

Step 6 • Binding and sleeve

1. Trim batting and backing even with the top.
2. Join the 6 Baltic navy binding strips (6 cm × WOF) end to end with diagonal seams into one strip about 630 cm long; you need 505 cm. Press it in half lengthwise, wrong sides together.
3. Hem the short ends of the sleeve with a 1 cm double hem. Fold it in half lengthwise, wrong sides together, and baste the raw edges to the top edge of the back, so the binding seam catches them.
4. Start halfway along one side and leave a 20 cm tail. Sew the binding to the front, raw edges together, with a 0.75 cm seam, mitring each corner as shown.
5. Join the two ends with a diagonal seam, finish sewing, turn the binding to the back and hand-stitch its fold over the seam. Push the lower fold of the sleeve up 1 cm, so a rod has room, and hand-stitch it to the back.
6. Add a label: your name, the year, and “Kogge”.




--- Suggested quilting lines



1 Sew across, right sides together




2 Trim, press the seam open




3 Press in half lengthwise


Joining the binding strips. The pale strip is shown wrong side up.



1 Stop one seam allowance short



2 Fold the strip up at 45°




3 Fold it down, sew from the edge

Mitring a corner. Turn the quilt and carry on down the next side.


Quarter-circle templates

Print these pages at 100% (“actual size”, not “fit to page”) and measure the test square before you trace. Each template is a quarter disc around the corner of the finished unit. Its straight edges include the seam allowance and go on the raw edges of the background square; the dashed lines are the seam lines.


Templates 4 and 5 are too big for one page and come in parts. Cut each part along its edges marked ∞, lay it over the grey strip of the next part so the cut edge sits on the dashed line and the short marks meet, and tape. Then cut the template out along its outline. If you prefer, draw these two yourself on paper: draw two lines at right angles for the straight edges and mark the corner dot 0.75 cm in from both lines. Pierce a strip of card near one end and again at the radius, pin the first hole on the dot, put a pencil through the second and draw the arc from line to line.



Test square: must measure 5 × 5 cm



Template 1 · radius 5 cm · trace 28: 8 sailcloth (Q1), 4 Baltic navy (Q2), 2 Hanse red (Q3), 12 aqua (Q4), 2 oak brown (Q5)



Template 2 · radius 10 cm · trace 15: 12 teal (Q4), 2 copper (Q5), 1 Hanse red (Q6)


Template 3

radius 15 cm

• = corner of the finished unit


dashed = seam lines

Template 3 · radius 15 cm · trace 2: 2 oak brown (Q5)





Template 4


part 2 of 2



Template 4, part 2 of 2. Check that the square measures 2 cm before you cut.



Template 5, part 1 of 4. Check that the square measures 2 cm before you cut. Template 5 · radius 25 cm · trace 1: 1 sun gold (Q6).




Template 5



part 2 of 4




cut



Template 5, part 2 of 4. Check that the square measures 2 cm before you cut.




Template 5, part 3 of 4. Check that the square measures 2 cm before you cut.



Template 5

part 4 of 4



Template 5, part 4 of 4. Check that the square measures 2 cm before you cut.

Layout chart


The whole quilt with every piece and unit code. Brackets mark the sections.



REFERENCE

Colour your own

Print this page and try your own colours before you buy fabric. Every line is a seam or the edge of a quarter disc.



Kogge is an original quilt design, inspired by the modular geometric illustrations of Siggi Eggertsson and by the Bremen cog of about 1380. It is not affiliated with or endorsed by the artist. Every measurement, cutting plan and diagram in this pattern is generated from one design grid and checked against it.

Pattern version 1.1, October 2026. Please read all instructions before you start.